



#### FC Landfill Energy Frederick County, Maryland

Presented by:

Mehal M. Trivedi – Project Manager Division of Utilities & Solid Waste Management Frederick County, Maryland Joe Ventre, Vice President Energenic, LLC

January 19, 2011







A project to design, construct, own, operate and maintain a 2.1 megawatt landfill gas to energy facility located at Reichs Ford Sanitary Landfill in Frederick County, Maryland



















## **Reichs Ford Road Sanitary Landfill**



- Began accepting waste in 1969
- 530-acre site with a design capacity in excess of 2.75 million tons of MSW over two sites
  - Site A closed and capped, with an LFG collection and control system installed in 1998
  - Site B currently open and expected to meet the County's disposal needs through 2045
- Two previous attempts to build/operate a landfill gas to energy (LFGTE) project were unsuccessful


















#### **Reichs Ford Road Sanitary Landfill**




14<sup>th</sup> Annual LMOP Conference and Project Expo – Frederick County Landfill Energy, LLC



#### Construction





Site B Vertical Expansion airspace and 28 wells





















- As built drawings, periodic aerial surveys help locate
  - Liner limits, waste depths
  - Leachate collection system
    - Laterals, headers
    - Trenches
    - Cleanouts
- Integrate 12 year old Site A LFGCC
  - 72 extraction wells in good condition, were balanced in-house
  - Blowers, flare upgrades were necessary

















## Landfill Gas Project History



- Apr. 1997 Letter from DPW Director: EPA's preliminary results find Reichs Ford promising candidate for LFGTE
  - Could generate 2.2 MW of electricity
- Dec.1998 Site A's LFG system in place
  - Actual construction cost = ~\$1M; Annual O&M = <\$5K; no revenue</p>
- Aug. 1999 County issued RFP for Feasibility Assessment for LFGTE
  - Evaluate the generation and recovery potential
  - Potential end uses
  - Approximate costs

















## Landfill Gas Project History



- Jul. 2001 Final Report
  - Identified 3 nearby gas end users/sales
  - Electricity generation up to 3Mw, local utility could be purchaser
  - On-site use gas up to \$13K/Yr, electric up to \$75K/Yr
  - Green power, greenhouses
- Jul. 2001 Summary of Findings: Reichs Ford good LFGTE candidate
- Dec. 2001 Attended LMOP Conference; solicited expressions of interest from attendees
- Jan. Jul. 2002 Received 16 responses
- Oct. 2002 Drafted RFP for internal review
- Project put "on hold" a low priority

















#### Landfill Gas Project History



- Nov. 2003 County issued RFP for design/build services
- Jan. 2004 Technical Proposals opened and selection made
- Apr. 2005 First design progress meeting
- Sept. 2005 Contractor walks away from negotiations
- Feb. 2007 Curtis Engine, a contractor partner, planned to pick up contract but waits for another RFP to be issued
- Sept. 2007 Northeast Maryland Waste Disposal Authority issues RFP for development, ownership, operations, and purchase; no award
- 2008 Northeast Maryland Waste Disposal Authority issues another RFP for development, ownership, operations, and purchase
- March 2008 Northeast Maryland Waste Disposal Authority initiates
  Interconnection Study
- Feb. 2009 FC Landfill Energy, LLC awarded contract

















## **Project Team**



- Frederick County Division of Utilities & Solid Waste Management owner/operator of Reichs Ford Sanitary Landfill
- Northeast Maryland Waste Disposal Authority joint project sponsor with Frederick County – procurement and contract administration
- Energenic, LLC Sole owner of FC Landfill Energy, LLC
- FC Landfill Energy, LLC special purpose company created to own and operate energy generating facility
  - Energenic, LLC Project Developer, Project Manager
  - EA Engineering, Science, and Technology, Inc. environmental permitting
  - South Jersey Energy Solutions, LLC power and environmental attribute marketing
  - DCO Energy, LLC EPC/O&M contractor
    - Industry and Energy Associates, LLC (now part of Stantec) civil, structural, mechanical, electrical and control design
    - EA Engineering, Science, and Technology, Inc. gas collection system design

















## **Contract Details and Project Specifications**



- FC Landfill Energy, LLC
  - Wholly owned subsidiary of Energenic, LLC, a partnership between long-term business partners South Jersey Energy Solutions, LLC and DCO Energy, LLC
- Major Design/Build Elements
  - New LFG collection system for uncapped and active Area B
  - Integration of the new Area B collection system with the existing Area A system and flare
  - Upgrades to existing flare system
  - New LFG conditioning systems and blowers
  - Two containerized reciprocating internal combustion engine-driven generators
    - Equipped with exhaust silencers and housed in sound-absorbing enclosures to suppress noise propagation beyond the fence line
  - Power transformation equipment and utility interconnection
















14th Annual LMOP Conference and Project Expo – Frederick County Landfill Energy, LLC



## **Site General Arrangement**









# **Project Permitting**



- Site development permitting
  - Frederick County Site Plan Approval and Stormwater Approval
  - Catoctin and Frederick Soil Conservation District (E&S) Approval
- EA anticipated a new Site Plan would not be required for the project and it would be covered under the existing Plan
- County Planning and Zoning determined part of the project covered under existing Plan and part required a new Site Plan – development/approval required 3-4 months
- Lessons learned
  - Meet with permitting staff earlier in the project process
  - Ask for written concurrence of permitting pathway
  - Communicate with all stakeholders frequently

















## Permit Summary



- County
  - Site Plan, Forest Resource and Adequate Public Facility Ordinance
  - Site Improvement Plans, Zoning/Landuse
  - SWM Plans, Easements
  - Grading Permit, Soil Conservation
  - Building Permits (Electric, Mechanical, Plumbing)
- State, Federal
  - Permit to Construct Flare, Engines
  - Operating Permits Title V, Refuse Disposal
  - Green House Gas Reporting

















# **Overview of Project Timeline**



- Feb. 2009 Construction, Operations & Maintenance Agreement Executed
- May 2009 MDE Permit Application
- Design of collection system (EA Engineering, Science, and Technology) and electrical generation equipment (DCO) occurred in parallel
- Jan. 2010 All Permits Approved; Start of Construction Activities
- Mar. 2010 Completion of Well Field Construction
- Apr. 2010 Substantial Completion
- May 2010 Commercial Operations
- Aug. 2010 Final Completion


















## **Operations Begin**



- May 31, 2010 Operations began
- Sept. 9, 2010 Frederick County Commissioners, the Maryland Energy Administration and the EPA recognized the plant





















# **Current Operations**



- Since Commercial Operation in May 2010 till Dec 2010:
  - Total Generated Electricity: 9,830,215 kW
  - Plant Availability: 91.8%
  - Total Landfill Gas Utilized: 258,996,689 ft<sup>3</sup>



















# **Key Project Aspects**



- Successful team effort between developer, the Authority, and the County
- Early initiation of the Interconnection Study by the Northeast Maryland Waste Disposal Authority
- Land GEM models created by Energenic during development phase meet the gas demands of engines
- Gas conditioning designed to remove moisture and particle contaminates and chill the LFG before entering engines
- Controls interface with landfill's existing LFG collection and flare system
- High plant availability
  - Well-field balancing at startup
  - Remote monitoring and data storage capabilities















#### **Questions ???**



















